



Przedsiębiorstwo Produkcji Sprężarek Airpol Sp. z o.o.

ul. Nieszawska 15c, 61-021 Poznań, Polska

Dział Sprzedaży +48 61 650 45 67, airpol@airpol.com.pl

Dział Serwisu + 48 694 477 251, +48 61 650 45 75, serwis@airpol.com.pl

www.airpol.com.pl

Compressor certificate

1. Manufacturer:	Przedsiębiorstwo Produkcji Sprężarek Airpol Sp. z o.o. ul. Nieszawska 15c, 61 – 021Poznań, Poland
2. Compressor type:	Deno 30
3. Factory number:	S09450625
4. Capacity:	325 m ³ /h
5. Motor power:	30 kW
6. Overpressure:	8 bar
7. Weight :	720 kg
8. Year:	2025

Compressor is made according to the manufacturing and acceptance requirement and comply with the norms and directives specified in the attached declaration of conformity.

Stamp

Date

16.06.2025

Signature of the factory acceptance inspector

PRZEDSIĘBIORSTWO
PRODUKCJI SPRĘŻAREK
"AIRPOL" Spółka z o.o.
61-021 Poznań, ul. Nieszawska 15 c
tel. 61 650-45-67,
NIP 782-00-06-643 Regon 630517391

SZEF DZIAŁU
ZAPEWNIENIA JAKOŚCI

mgr inż. Robert Hoffa



Przedsiębiorstwo Produkcji Sprężarek Airpol Sp. z o.o.

ul. Nieszawska 15c, 61-021 Poznań, Polska

Dział Sprzedaży +48 61 650 45 67, airpol@airpol.com.pl
Dział Serwisu + 48 694 477 251, +48 61 650 45 75, serwis@airpol.com.pl

www.airpol.com.pl

DECLARATION OF CONFORMITY EC

Hereby declares with full responsibility, that the following products:

Compressor:

Deno 30

S09450625

to which this declaration applies, conform with:

- 2014/68/EU Pressure Equipment Directive
- 2006/42/EC Machinery Directive
- 2014/35/EU Low Voltage Directive
- 2014/30/EU Electromagnetic Compatibility Directive

It comply with the harmonized standards: EN ISO 12100:2012, EN 60204-1:2018-12
EN IEC 61000-6-4:2019-12, EN-1012-1:2011, PN-N- 01307:1994

The compressor has been marked with the following marking:



President

(-) Marek Jajeśniak

Poznań, 2025-06-16

Customer: Deno Compressors B.V.
Compressor: 30,0 kW air cooled
Controller: MS 686
Electric motor HOYER 30,0 kW
Type of start Y/Δ

Drawing No:
Serial No: S09450625

Tested by:
Date: 13. 06. 2025

Electrical installation marked code IP54 according to standard PN-EN-60529.

Complies with safety regulations according to standards: PN-EN 60204-1:2010, PN-EN 60204-1:2010/AC:2011, PN-EN 60947-1:2010, PN-EN 60947-1:2010/A1:2011, PN-EN 1012-1:1999.

No	General check points	Result		
		Yes	No	n.a.
1.	The control box working properly	✓		
2.	Built according to specification of customer	✓		
3.	Built according to electrical drawing	✓		
4.	All components marked	✓		
5.	All wires marked	✓		
6.	Torques and fittings correct	✓		
7.	Controller working properly	✓		
8.	Parameters of controller set correctly	✓		
9.	Parameters of softstart set correctly			✓
10.	Parameters of frequency controller set correctly			✓
11.	Heater, fan, light of electric box are correct			✓
12.	Name plate with number			✓
13.	Drawing of electric diagram in the electrical box	✓		
14.	Technical documentation – manual, drawings	✓		
15.	Cable glands mounted and properly tightened	✓		
16.	Control box painted and cleaned	✓		
17.	Control/display panel mounted correctly	✓		
18.	Fuses are correct	✓		
19.	Control lamps are correct			✓
20.	Switches are correct	✓		
No	Check points according to the norms	Result		
21.	Size of power and control cables correct	✓		
22.	Size of fuses and transformer correct	✓		
23.	Protective grounding PE correct	✓		
24.	Bare cables secured	✓		
25.	Main switch mounted correctly			✓
27.	Emergency STOP pushbutton correctly	✓		
28.	Thermal overload of electric motors are correct	✓		
29.	Safety settings of controller/softstart/frequency converter are correct	✓		
30.	There are no loose cables	✓		
31.	Other			

PRZEDSIĘBIORSTWO
PRODUKCJI SPRĘŻAREK
"AIRPOL" S. JAKOŚĆ
61-021 Poznań, ul. Nieszawska 15c
tel. 61 650-45-67
NIP 7820006643 Regon 630517391

SZEF DZIAŁU
ZAPEWNIENIA JAKOŚCI

mgr inż. Robert Hoffa

NIP 7820006643

REGON 630517391

Konto bankowe 25 1030 1247 0000 0000 8381 4004

Dane o rejestracji Sąd Rejonowy w Poznaniu VIII Wydział Gospodarczy Krajowego Rejestru Sądowego, KRS 67746

Kapitał zakładowy 2.370.000 PLN

CHECK LIST FOR TESTING

Order:	Date: 13. 06. 2025		
Compressor: DENO 30	S09450625		
E-motor type: HMC3 200L 1-2	DK1246300005		
Kw/rpm/voltage/Amp @ 50Hz:			
Kw/rpm/voltage/Amp @ 60Hz:	30/480/43,9/3540		
Air end type: DSU70	8365		
Year of make:	2025		
Max.rpm	8 000		
Cooler type:	R14367		
Factory number:	S0945		
Test date:	24 bar/water		
V-belt type and quantity:	XPA 1400		
Checks caried out:			
Checking of the fittings and elektical connections	ok.		
Control of the all thermal settings		60	A
Control of value of the fuses in the line: F1/F2/F3		2/2/2	A
Check the value of the transformer protection fuses F4/F5/F6/F7		2/2/2/2	A
Check the oil level and recheck after testing	ok.		
Check the sense of rotation of the compressor and fan	ok.		
Control of the setting of the minimum pressue valve (5 bar)		5,0	bar
Connection to the air receiver	ok.		
Setting of the final pressure		8	bar
Setting of the differential pressure		2	bar
Running as start-stop for 10'	ok.		
Running unload until the automatic stop. Repeat twice	ok.		
Turn the compressor off using the emercency stop direct after starting in order to check any oil leaking from the filter. Repeat twice	ok.		
Running for 2 hours at pressure lower than the maximum pressure and record of the maximum temperature	ok.	85	°C
Running contact test: R6=10=NO	ok.		
Common alarm test: R5=2=NC	ok.		
High pressure alarm:		9	bar
High pressure warning:		8,5	bar
High temperature alarm:		110	°C
High temperature warning:		105	°C
Air end speed loading:			rpm
Motor speed loading:			rpm
Stop time:		8	sec
Idle run time:		240	sec
Oil pressure at 8,0 bar		8,2	bar
Safety valve type and setting:		11	bar
Check of the oil in line	ok.		
Check the presence of any oil leaking	ok.		
Check the alignment and tighten screws and flanges	ok.		
Check the required parameters			
TEST DATA:			
air receiver:1000 liter			
time: 69 sec 2-8 bar			
calc. cap.: 313 m3/hr @ 50Hz, 391V			
Measured Amp at max delivery pressure 8,0 bar:		54	A
Temperatura after load and idle run		72	°C
Pully motor/compressor		150/132	mm

Performed by:

PRZEDSIĘWZIENIE
PRODUKCJI SPRĘŻENIA
"AIRPOL" Sp. z o.o.
61-021 Poznań, ul. Nieszawskiej 10
tel. 61 650-45-67,
NIP 763-05-05-543 Regon 53015131

SZEF DZIAŁU
ZAPEWNIENIA JAKOŚCI

mgr inż. Robert Hoffa

Przedsiębiorstwo Produkcji Sprężarek Airpol Sp. z o.o. Ul. Nieszawska 15c 61-021 Poznań	Test report No: DZJ/13/06/2025	Date: 13.06.2025
Quality Department		

Pressure test

The subject of the research:

Cooler type : **R 14367**

Factory numbers: **S0945**

Maximum working pressure: **16 bar**

Test pressure: **24 bar**

Medium: **water**

Test manometer: No AP 306 (Ø160, range 0 – 25 bar).

Positive test.

PRZEDSIĘBIORSTWO
PRODUKCJI SPRĘŻAREK
"AIRPOL" Sp. z o.o.
61-021 Poznań, ul. Nieszawska 15c
tel. 61 650-45-67,
NIP 762-00-06-643 Regon 1430517321

SZEF DZIAŁU
ZAPEWNIENIA JAKOŚCI

mgr inż. Robert Hoffa



Przedsiębiorstwo Produkcji Sprężarek Airpol Sp. z o.o.

ul. Nieszawska 15c, 61-021 Poznań, Polska

Dział Sprzedaży +48 61 650 45 67, airpol@airpol.com.pl

Dział Serwisu + 48 694 477 251, +48 61 650 45 75, serwis@airpol.com.pl

www.airpol.com.pl

Pressure vessel passport

Type: KS-50-12

INDEX: MCA8461

Serial number: 19410, 19411, 19412.



Przedsiębiorstwo Produkcji Sprężarek Airpol Sp. z o.o.

ul. Nieszawska 15c, 61-021 Poznań, Polska

Dział Sprzedaży +48 61 650 45 67, airpol@airpol.com.pl
Dział Serwisu + 48 694 477 251, +48 61 650 45 75, serwis@airpol.com.pl

www.airpol.com.pl

DECLARATION OF CONFORMITY EU

We declare under sole responsibility that the product:

Pressure vessel for compressed air and oil

Type KS-50-12
serial no. **19410, 19411, 19412.**

to which this declaration refers, conforms to the following:
Pressure Equipment Directive 2014/68/UE.

Requirements: Technical Inspection Office Conditions: WUDT/UC/2003

Compliance evaluation procedure for module A2, cat: II

Test report: no. 62689/JN/016/04

Notified body:

UDT – CERT Technical Inspection Office
02- 353 Warszawa
ul. Szczęśliwicka 34
Notified body no 1433

The vessel was subjected to a water pressure test at pressure of 22 bar
The vessel is marked with the following symbol



and notified body number: 1433

President

(-) Marek Jajeśniak

Poznań, dnia 30.05.2025 r.

I. Technical description of the pressure equipment

1. Type: Constant pressure vessel
2. Type: KS-50-12
3. Serial number: **19410, 19411, 19412.**
4. Year of manufacture: 2025
5. Vessel technical specification

Maximum working pressure	PS (bar)	12
Maximum test pressure	PT(bar)	22
Capacity	V (L)	50
Calculated pressure	PD(bar)	12
Minimum operating temperature	TSmin (°C)	0
Maximum operating temperature	TSmax(°C)	130
Permissible temperature	TD(°C)	130
Corrosion allowance	c2	0,5
Medium		Air, Oil
Factor for pressure test		Water
Factor category by 97/23/WE		2
The minimum wall thickness including c2:	mm	A= 2,2 B= 2,2
A - Shell B - Bottoms		

6. Conformity assessment procedure: Directive 2014/68/UE, Module A2, Category II.


7. Destiny: Storage tank

8. Drawing number: 780-155-000.

9. Number of manual: 07/2022

Manual has been compiled in language of the country of destination.

10. Nameplate:

 PRZEDSIĘBIORSTWO PRODUKCJI SPRĘŻAREK AIRPOL Sp. z o.o.		
61-021 Poznań, ul. Nieszawska 15c, Poland, tel. +48 61/650 45 67 www.airpol.com.pl		
ZBIORNIK CIŚNIENIOWY - PRESSURE VESSEL		
Nr fabr.-Serial No.	Typ-Type	Rok bud.-Year
PT (bar)	PS (bar)	V (L)
TSmax(°C)	Medium	TSmin (°C)
	olej + powietrze / oil + air	
Data próby ciśn.-Pressure test date		
 1433		

II. Vessel construction materials, drawing number: 580-155-000

Lp.	Name	Character of the material	Norm	Nominal thickness	Type of document/ Approved	Approval number	Heat	PMA number
1.	Mantle	S355J2	EN-10051	3	Atest 3.1	21/338307 01	46908	01/2016
2.	Bottoms 324x3	S355J2	PN-64/M-35411 / DIN28013	3	Atest 3.1	1193/1/T/2025	41894	01//2016
3.	Collar	S355J2	EN-10051	25	Atest 3.1	31384/2020	307243-1	01/2016
4.	Cover:	S355J2	EN-10051	20	Atest 3.1	210/AHK/22/1-1 30461/2024	605264 32255	01/2016
5.	Connector G1/4	S355J2	EN-10025	Ø 25	Atest 3.1	82121650 552023EA69/2017	552023	03//2016
6.	Connector G3/4	S355J2	EN-10025	Ø 40	Atest 3.1	10987/0/2020	386671	03//2016
7.	Connector G1	S355J2	EN-10025	Ø 45	Atest 3.1	82781573 571109E329/2019	571109	03//2016
8.	Connector M52x2	S355J2H	EN-10216-3	Ø 54,0x8,8	Atest 3.1	20923/1/2022	21243	02/2016
9.	Connectors: pipe M36x1,5	S355J2	EN-10210	Ø 51x10	Atest 3.1	41496/1/2015	53648	02/2016
10.	Elbow 42,4x3,6	P265GH	EN-10253	Ø 42,4x3,6	Atest 3.1	6133/1/2016	55322	-
11.	Pipe 48,3x3,2	P235TR2	EN 10216-3	Ø 48,3x3,2	Atest 3.1	21234/1/2022	21750	-
12.	Welding wire	G4Si1	EN ISO 14341-A	Ø1,2	Atest 3.1	308098	00640569	-

During the entire manufacturing process the division of the base material there shall be surveillance of transfer characteristics of the material to identify products manufactured.
Moved traits: heat number, name of material.

III. Summary statement of welding technology.

List of welding technology

Lp.	Number of connections	Number WPS	Number WPQR	Welding method	Type of connections
1.	5	5/135/17	01 202 PL-V-17 0384	135	BW
2.	5	2/135/17	5/135/13 01 202 PL-V-16 0681	135	BW
3.	2	7/135/17	01 202 PL-V-17 0801	135	FW
4.	2	10/135/17	01 202 PL-V-17 0384	135	FW
5.	7	6/135/17	01 202 PL-V-17 0383	135	BW / FW


IV. Quality control guidelines for drawing number: 780-155-000

Lp.	Range of research	Test method	Class technology and research	Criteria for evaluation of test results
		VT	PN-EN 970	PN-EN ISO 5817:2009/Ap1:2009 WUDT-UC-WO-W/11
1	100%	+	+	Positive, connectors meet the required level of quality „B“


V. Attachments:

1. Manual number: 07/2022.
2. Instructions WPS attached to the documentation of the manufacturer and UDT-CERT.
3. PMA attached to the documentation of the manufacturer and UDT-CERT.
4. Certified welders attached to the documentation of the manufacturer and UDT-CERT
5. Engineering drawing.

Robert Hoffa



Certyfikaty kompetencji nr:
TSP-00701-VT2-01
2527-00701-PED-VT2-00



PROTOKÓŁ BADANIA WIZUALNEGO VISUAL INSPECTION PROTOCOL	Nr / No: VT-19410-19412
	Strona 1 z 1 / Page 1 of 1
Obiekt badany Tested product	Zbiornik ciśnieniowy / Pressure vessel KS-50-12 Nr / No: 19410, 19411, 19412 Wykonany wg rys. nr 780-155-000 / made as per drawing no. 780-155-000
Zakres badań Scope of testing	Badaniom poddano złącza spawane wykonane podczas wytwarzania zbiornika: 100% spoin + SWC + 10 mm po obu stronach. Testing covered welded T and Butt joints made during the manufacture of the vessel: 100% welds + SWC + 10 mm on both sides.
Stan powierzchni badanej Condition of the test surface	Surowa po spawaniu, oczyszczona z luźnych zanieczyszczeń, sucha. Raw after welding, cleaned of loose dirt, dry.
Warunki badania Test conditions	Natężenie światła >700 lx / Light intensity >700 lx, odległość badania ~500 mm / Test distance ~500 mm, kąt patrzenia > 30° / Viewing angle > 30° temperatura otoczenia 20°C / Ambient temperature 20°C
Wyposażenie badawcze i pomiarowe Testing and measurement equipment	Miernik światła białego L-20A nr: 1944/2001 White light meter L-20A no.: 1944/2001, termometr: TES1312A nr: 080117400 / Thermometer: TES1312A no.: 080117400 suwmiarka nr: 15151048 / slide caliper no.: 15151048, spoinomierz INSIZE 4838-1 nr: 2205121516 / weld gauge INSIZE 4838-1 no.: 2205121516, przymiar, lupa, latarka, lusterko. / gauge, magnifying glass, flashlight, mirror.
Metoda spawania /Welding method	135
Pozycja spawania /Welding position	PA/PB
Gatunek materiału /Material grade	S355J2/P355GH/P265GH/P355NL1/P355NL2
Obróbka cieplna po spawaniu Heat treatment after welding	Bez obróbki No treatment
Instrukcja badania /Testing instructions	1/VT/2014
Przepis / poziom akceptacji Acceptance provision/level	PN-EN ISO 5817 / poziom jakości B PN-EN ISO 5817 / quality level B
Stosowane normy/Applied standards	PN-EN 13018, PN-EN ISO 17637, PN-EN ISO 5817, PN-EN ISO 6520-1
Wynik badania/Test result	W wyniku przeprowadzonych badań nie stwierdzono niedopuszczalnych niezgodności. Testing found no unacceptable non-compliance. Pozytywny – spełnia poziom jakości B / Positive – meets the quality level B
Miejsce i data badania: Place and date of the test:	Badania wykonał: / Tests performed by: Opracował: Robert Hoffa 
Poznań, 30.05.2025r.	Certyfikaty kompetencji nr: Competence certificates no.: TSP-00701-VT2-01 2527-00701-PED-VT2-00

Projekt, wytworzenie, badanie, eksploatacja według warunków Urzędu Dozoru Technicznego WUD/TUC/2003



Charakterystyka techniczna		Aparat
Wytwórca		Pn 1969j
Ciepłota właściwa		12
Najwyższe dopuszczalne ciśnienie		P5 (topr)
ciężenie próbne		P7 (topr)
Najwyższa temperatura robocza		T5 max (Tf)
Najniższa temperatura robocza		T5 min (Tf)
Pojemność zbiornika		V II)
Medium		Powietrze, olej
Wskazywniki wytrzymałości złącza sprężonego		Zb
Różnice na korozję		C2 (um)
Badanie NBT WDTNIE/2003 (zgodnie ze standardem)		Ow- spom
Badanie NBT WDTNIE/2003 (zgodnie ze standardem)		Badanie R/TOT













21	Podziałka sprężyna	12	PNH-82008	5,8				12	MPD0006	0,048 kg
20	Śruba	12	PH-EN ISO 4032	5,8				M12x30	MSR050	0,511 kg
19	Ni	4	ISO 1951	Al				3x8	NI10004	0,001 kg
18	Kolano numeryczne	1	01K0405	P265EH	PH-EN 10228-2	EN 10253-2		42x43x8	PM20023	0,288 kg
17	Talarka znośowa	1	993-00-008	Al					MC2C80	0,007 kg
16	Kolmierz 1/324	1	780-56-005	S355J2-N	PH-EN 10025-2	PH-EN 10029			MCW1539	10,439 kg
15	Podkładka	1	780-56-002	S355J2-N	PH-EN 10025-2	PH-EN 10051 PH-EN 10029			MCW4845	0,693 kg
14	Kraciec H30x15	1	780-54-008	S355J2H	PH-EN 10270	PH-EN 10270-2			PM00331	0,264 kg
13	Wspornik	2	780-33-006	S235JR	PH-EN 10025-2	PH-EN 10029			MCW624	4,086 kg
12	Pokrętło	1	780-33-004	S355J2-N	PH-EN 10025-2	PH-EN 10051 PH-EN 10029			MCW620	9,078 kg
11	Plaszcz	1	780-155-010	S355J2-N	PH-EN 10025-2	PH-EN 10029			MCJ6440	13,256 kg
10	Rura	1	780-155-006	S355J2H	PH-EN 10025-2	PH-EN 10270			MCB0645	0,700 kg
9	Dno elipsoidalne H24x3 H=101	1	780-143-001	S355J2-N	PH-EN 10025-2	PH-75M-35x12			MC65594	2,536 kg
8	Kraciec M30x2	1	780-142-002	S355J2B3	PH-EN 10025-2	PH-EN 10270			MC64332	0,56 kg
7	Kraciec	1	780-14-0067	S355J2	PH-EN 10025-2	PH-EN 10060			MCW2243	0,043 kg
6	Pręgarada	1	780-14-00065	S355JR	PH-EN 10025-2	PH-EN 10029			MCW457	3,177 kg
5	Kraciec	1	780-11-00068	S355J2	PH-EN 10273	PH-EN 10060			MCW0919	0,888 kg
4	Kraciec M52x2	1	714-00-131	S135					MS502	0,208 kg
3	Stopka pod łódź znoś	1	580-30-011	S235JR	PH-EN 10025-2	PH-EN 10029			MCW6712	0,031 kg
2	Kraciec G34x1	1	162-30-004	S355J2H	PH-EN 10270	PH-EN 10270			MCW0866	0,716 kg
1	Kraciec G1/2"	1	140-03-033	S355J2B3	PH-EN 10025-2	PH-EN 10270			MCW1562	0,94 kg
LP	Nazwa części	IL	NR RYS/NUMERA	MATERIAŁ	NUMERA PHT	NUMERA PRZŁ			NUMERA	MASA

OBOWIĄZUJE DO PRODUKCJI I SERWISU		Data	Materiał	Podpis	Kopie
	Konstruował	18.04.2022			46,560 kg
	Sprawił	R. Hoffa	Wymiary:		A2
	Zawierzał	A. Jakubczak	Norma:		Pozostała
	Wykonawca	Przedsiębiorstwo Produkcyjne Sprężarek Alpard, sp. z o.o. ul. Nieszawska 15c 61-021 Poznań	Wyroby		15
QR	TO	Uzł	Nazwa	Numer rysunku	Arkusze
			Zbiornik KS-50-12	780-155-000	Indeks
			A		MC8461



Szczegół
Wykonanie dopuszczalne





OBOWIAZUJE DO PRODUKCJI SERII INEJ		Data	Podpis	
Konstruował	M. Kosmalwski	18.03.2022		
Sprawdził	R. Hoffa			
Zatwierdził	A. Jakubczak			
Przedsiębiorstwo Produkcji Sprężarek Egzemplarz rejestracyjny Alpod. sp. z o.o. ul. Nieszawska 15c 61-021 Poznań				
DR TO IZJ	Nazwa Zbiornik KS-50-12	Zmiana A	Numer rysunku 780-155-000	Indeks MC18461
				Arkusz 2
				1:1
				Wyrób KS-50-12
				Norma
				Wymiary
				Forma
				Waga
				46,560 kg



Przedsiębiorstwo Produkcji Sprężarek Airpol Sp. z o.o.

ul. Nieszawska 15c, 61-021 Poznań, Polska

Dział Sprzedaży +48 61 650 45 67, airpol@airpol.com.pl

Dział Serwisu + 48 694 477 251, +48 61 650 45 75, serwis@airpol.com.pl

www.airpol.com.pl

Operating manual

No. 07/2022

Vessel

1. Intended use

The pressure vessels listed may be only used in compressed air or argon systems + oil.
The pressure vessels have oil separator function.

2. Safety requirements

Vessels may not be used for purposes other than those stated in the device passport or on the rating plate.
Do not exceed parameters stated in the passport or on the rating plate.
Vessel equipment should comply with the regulations in force.
Vessels may be transported only in ambient pressure relief conditions and without the working factor.

3. Packing, storage and transport

Vessels is packed on pallets for transport. Vessels may be transported by any means of transport.
Loading and transport should be performed in compliance with the appropriate regulations.
Connector pipes have been secured with plugs.
Vessels should be stored in dry, covered places and secured from moving.

4. Location and installation

The vessel should be set in a covered area. It can operate in temperatures specified in the data sheet and on the nameplate.

It should be set so that it provides access to all parts of the vessel during testing, cleaning or revision.

The vessel must have: safety valve against pressure increase above the allowable pressure with respect to supply sources, gauge, gauge tap, condensate drain.

The connection between the safety valve and the vessel can not be of smaller diameter than the valve inlet.

In particular, the safety valve is important that should be mounted on the vessel without interpositioning possible; the valve should be adjusted and sealed for the pressure lower than or equal to the admissible pressure, the value of this pressure should be marked on the pressure gauge with a red line.

Operation of the safety valve should be checked according to the safety valve instructions.
Between the vessel and the safety valve, a shut-off valve must not be installed.

The installation should prevent forces and bending moments (from the system) from being transferred onto the stub-pipes.

Rating plate should be well visible at all times.

Designed legs are adjusted to the weight of the vessel (including the weight during the pressure test).

5. Vessel operation

5.1. Conditions of putting the vessel in operation

The vessel can be put in operation if it:

- does not pose any threat to the safety of the public and the surroundings
- is fully equipped with appurtenances and safety devices according to any and all applicable regulations.
- has been tested and meets the requirements applicable for the country of the user.

5.2. Pre-operation activities

- Check if all the necessary equipment has been installed
- Check for any foreign substances or objects inside the vessel
- Check if the connections and cover mounting screws have been tightened properly

5.3. Putting in operation

Pressurize the vessel to the working pressure and check for leaks. If there are leaks, put the vessel out of operation, depressurize and remove the fault.

5.4. Using the vessels

Vessels must be used according to their intended use and any regulations in force.

In appropriate time intervals (according to the regulations in force), security valve should be inspected with the use of bubbling procedure.

Vessel equipment may be disassembled only when the pressure inside the vessel reaches the value of atmospheric pressure.

Repair any paint chips resulting from installation or operation

Vessels should be immediately disconnected in the case of:

- any leakages in removable connections
- vessel perforation
- failure or malfunction of vessel equipment (in particular of the security valve and manometer)
- the supply device control system not ensuring the working factor parameters within the accepted range.
- shell deformation
- exceeding the acceptable temperature

6. Vessel maintenance

Cleaning and maintenance should be performed so as not to damage the walls of the vessel and its fittings.

Cleaning must be safe for employees.

The vessel is cleaned inside and outside. Do not damage the exterior paint. Any losses must be repaired.

All work on the vessels must be performed only by designated trained personnel who know the pressure equipment regulations.

7. Vessel repairs

The vessel must not undergo any welding, and pressure parts must not be tampered with. Repairs may only be carried out by persons and companies with relevant authorizations.

Quality Manager



(-) Leszek Jakubczak



COMPONENTI PNEUMATICI E OLEODINAMICI

AIR TEK SRL

Via Pizzocaro, 15 36075 Montecchio Maggiore

TEL. 0444/492541 FAX 0444/497441

P.IVA E C.F. IT 02731550246

e-mail info@airteksrl.com web: www.airteksrl.com

DICHIARAZIONE DI CONFORMITÀ ai sensi dell'allegato IV della direttiva europea 2014/68/UE.

Declaration of conformity according to european directive 2014/68/UE annex IV.

VALVOLA DI SICUREZZA (IV° categoria) a scarico diretto per aria, gas inerti, vapore saturo, fluido tipo 2

Safety valve (class IV°) direct drain for air, inert gas, saturated vapor, fluid type 2

Numero di serie Serial Number	Scheda Collaudo n° Test Report No°	Nr. Pezzi Nr. of Pieces	Taratura Calibration (Bar)	Tipo di guarnizione Gasket type	Tipo Type
NS376	1814	65	11	VITON	VS34APED


Si dichiara che l'attrezzatura a pressione sopra descritta soddisfa i requisiti essenziali di sicurezza previsti nell'allegato I della Direttiva 2014/68/UE.

Si dichiara inoltre che la valvola ha superato con esito favorevole la prova idraulica a 37,75 bar e il controllo finale della taratura.

We declare that the pressure equipment described above satisfy the essential safety requirements of annex I of Directive 2014/68/UE annex IV

We also declares that the valve has passed the hydraulic test with a favorable outcome to 37.75 bar and the final check of the calibration.

COMPONENTI COMPONENTS	MATERIALI / MATERIAL
a) Corpo Valvola/Valve Body	CW614N UNI EN 12164
b) Guarnizione / Gasket	NBR - VITON
c) Otturatore / Shutter	CW614N UNI EN 12164
d) Ghiera / Ring Nut	CW614N UNI EN 12164
e) Molla / Spring	UNI EN 10270-1 DH
f) Spillo / Pin	UNI EN 10263-2 1.0303
g) Piastrina / Plate	ALLUMINIO / ALLUMINIUM
h) Anello / Ring	UNI EN 10270-1 SM



CARATTERISTICHE TECNICHE / TECHNICAL DATA	
Marchio del costruttore / Constructor's mark	AIR TEK
Diametro Nominale Ingresso / Nominal Diameter	3/4"
Diametro Orifizio / Orifice Diameter	13mm
Pressione Nominale Ingresso / Nominal Pressure	25 bar
Alzata / Lift (mm)	4,564
Coefficiente di efflusso / Discharge Coefficient K	0,78
Sovrapressione / Overpressure	10%
Scarto di chiusura / Closing variation	15%
Portata di scarico l/min Aria/Discharge flow rates AIR l/min	15310
Campo di taratura / Calibration Range	0,5 - 18 bar
Temperatura di esercizio / Working temperature HNBR	-30°C +150°C
Temperatura di esercizio / Working temperature NBR	-10°C +100°C
Temperatura di esercizio / Working temperature VITON	-20°C +250°C
Temperatura di esercizio / Working temperature EPDM	-40°C +150°C

Per la verifica della conformità alla direttiva sono state utilizzate le norme e le procedure di seguito indicate:

For the verification of compliance with the directive have been used the standards and procedures set out below:

Attestato di esame CE CE examination certificate	Modulo B/Form B tipo di produzione / production type n° PED-0948-PBprod-20243-23 ON 0948 TUV
Certificato di qualità della produzione Certificate of production quality assurance	Modulo D/Form D n° PED-0948-QSD-461-15 rev.4 del 20/12/21 ON 0948 TUV
Norme applicate Standards applied	Secondo direttiva 2014/68/UE - norma ISO 4126 According to directive 2014/68/UE - standard ISO 4126

Identificazione dati marcati sulla valvola / Identification data marked on the valve

Marchio CE / CE mark, Modello della valvola / Valve model, Individuazione dell'organismo notificato / Notified authority identification, Numero di serie / Serial number, Pressione di taratura in bar / Calibration pressure in bar, Pressione nominale / Nominal pressure, Diametro dell'orifizio / Orifice diameter, Portata di scarico in l/min / Discharge flow rates in l/min, Marchio del fabbricante / Constructor's mark.

Firma del fabbricante / Signature of the manufacturer

Montecchio Maggiore 15/10/2024


COPIA CONFIRMATA

Nome e indirizzo dell'organismo notificato Name and address of the notified authority	TUV ITALIA srl 0948 viale Fulvio Testi 280/6, 20126 (MI)
--	---



Via Pizzocaro, 15 36075 Montebelluna Maggiore VI
TEL. 0444/492541 FAX 0444/497441
P.IVA E C.F. IT 02731550246
e-mail: info@airtekstl.com web: www.airtekstl.com

INSTRUCTIONS FOR USE OF THE SAFETY VALVES

INSPECTION OF INCOMING PARTS

inspect goods upon receipt to make sure that packaging is intact. Should packaging be damaged, please notify AIR TEK and arrange to have the valve examined to make sure that it is in perfect condition.

CONFERENZA INTERNAZIONALE SULLA PREVENZIONE E L'ELIMINAZIONE

DECLARACIÓN DE CONFORMIDAD (con arreglo al anexo IV – directiva europea 2014/53/UE) / DECLARATION DE CONFORMITE (conformément à l'annexe IV de la Directive Européenne 2014/53/UE) (gemäß Beilage IV der europäischen Richtlinie 2014/53/UE).

Número de Serie/Numéro de série/Seriennummer	Fauille de test nr. Hoja de prueba nr. Testblatt nr.	No. Piezas N. de pièces Stückzahl	Calibracion Calibration Eichung	Junta Joint Dichtung	Familia Familie Familie
--	--	---	---------------------------------------	----------------------------	-------------------------------

[illegible]

MATERIALEN	MATERIEEL	MATERIAL
CW6184N UNI EN 12164	a) Cuerpo valvula/corpus soupape/ventielkoepel	
	b) Junta/joint/Oichtung	
HNBR – NBR – VITON – EPDM	c) Obturator/obturateur/verschluss	
CW6184N UNI EN 12164	d) Abrazadera/embutido/nutrimutter	
CW6184N UNI EN 12164	e) ressort/resort/feder	
UNI EN 10270-1, DH UNI EN 10270-3 1.4310		
NS	f) punzon/epingle/nadel	
UNI EN 10263-2	g) plaqueta/plaquette/streilen	
ALUMINIUM	h) Anello / Ring	
		UNI EN 10270-1 SW

CHARACTERISTICAS TECNICAS / CARACTERISTIQUES TECHNIQUES / TECHNISCHE EIGENSCHAFTEN	AIR TEK
Marca del fabricante Sigle du constructeur/ Erzeuger sigel	
D.N. de acceso/ D.N. entrée/ D.N. Eingang	
Diámetro agujero/ Diámetro orificio/Oeffnungsdurchmesser	
P.N. de acceso/ P.N. entrée / P.N. Eingang	25 bar
Elevation / Levee/ Hub mm	
K código de flujo/ k coeffic. de dépense/ K Abflusskoeffizient	
Sobrepresión/ Surpression/ Ueberdruck	
Desviación de cierre / Ecart de fermeture/ Verschussabweichung	
Descarga/débit d'evacuation/durchfluss /l/min	
Calibrado/ Champ d'etalonnage/Eichungsbereich	0.5 – 20 bar
Temperatura d'ejercicio/ Température d'exercice/ Betriebstemperatur	-30°C +150°C
Temperatura d'ejercicio/ Température d'exercice/ Betriebstemperatur	-30°C +90°C
Temperatura d'ejercicio/ Température d'exercice/ Betriebstemperatur	-10°C
Temperatura d'ejercicio/ Température d'exercice/ Betriebstemperatur	+250°C
Temperatura d'ejercicio/ Température d'exercice/ Betriebstemperatur	-40°C
Temperatura d'ejercicio/ Température d'exercice/ Betriebstemperatur	+150°C

Para comprobar la conformidad con la directiva, se han utilizado las normas y procedimientos indicados seguidamente; / pour la vérification de la conformité à la directive, nous avons utilisé les normes et les procédures indiquées ci-dessous; / Zwecks der Überprüfung der Einhaltung der Richtlinie sind folgende Normen und Verfahren angewandt worden:

Certificado de examen CE del tipo/ Attestation d'examen CE du type EG-Prüfzeugnis des Typs	Modulo B/Module B / Formular B N° 0537/02/CE - 28/02/2013 ON 01.00 INAIL N° 0539/02/CE - 28/02/2013 ON 01.00 INAIL
Certificado de calidad de la producción/ Zertifikat der Produktionsqualität	Formulario de Modulo B / Formular D N° 0540/02/CE - 28/02/2013 ON 01.00 INAIL Via Contrassegno Via Contrassegno 125 Sexto S. Giovanni (MI)
Normas aplicadas / Normes appliquées/Angewandte Vorschriften	Según directiva / D'après la directive / Entsprechend der Richtlinie 2014/68/EU – ISO A126-1

Lugar y fecha/lieu et date/Ort und datum

Firma del fabbricante/Segnatura du fabricant/Unterschrift des Herstellers

MONTECCHIO MAGGIORE

AIR TEK S.r.l.